

Safety Alert



Fitting Ply to Top Storey Frames (update)

The Hazard

Working at Heights without adequate fall protection when nailing ply to the top floor frame of a two-storey home.



The Risk

Risk Score: High

Possible long term injury or death resulting from a “Fall from Heights”.

What needs to be done?

Hudson Homes

The reverse build process requires Framing Carpenters to complete the final fixing of ply by returning to site after the scaffold has been erected.

Framing Carpenters

Ply may be **tacked** onto two storey frames via a step ladder, as long as the worker remains inside the protective frame and first floor (only one arm maybe extended outside the frame). **Final fixing of ply must be completed from the scaffold.**